

# Joint Development Area (JDA) Block B-17 Field Development Project: Multiple Jacket Lifts

## DATE

October 2017

## BACKGROUND

In October 2017 KTL Offshore was awarded the contract to design, manufacture and test 35 heavy lift slings for the jacket lifting phase of the JDA Block 17 project in the Gulf of Thailand. Due to their compact terminations, lighter weight and easier handling characteristics as compared to hand spliced cable laid slings, the customer selected the KimLock resin terminated cable laid sling as their preferred choice for this project.

The Joint Development Area (JDA) Blocks B-17 & C-19 and B-17-01 Integrated Development Project involves the phased development of gas and condensate fields in blocks covering a 4,700km<sup>2</sup> area south of the Gulf of Thailand off the coast of Thailand and Malaysia. The water depths range between 55m and 65m. These blocks contain a total of 18 gas fields.



## JDA B-17 01 Project, Thailand & Malaysia, October 2017 KimLock® Cable Laid Resin Terminated Slings

### SCOPE OF SUPPLY:

KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 20.00 m; x2 lengths.  
KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 19.90 m; x1 length.  
KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 19.80 m; x1 length.  
KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 19.60 m; x2 lengths.  
KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 19.50 m; x3 lengths.  
KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 19.40 m; x1 length.  
KimLock® cable laid resin terminated sling; 238mm dia; CSBL 2,477 MT; nominal length 19.20 m; x2 lengths.  
KimLock® cable laid resin terminated sling; 168mm dia; CSBL 1,254 MT; nominal length 46.00 m; x4 lengths.  
KimLock® cable laid resin terminated sling; 168mm dia; CSBL 1.254 MT; nominal length 50.00 m; x6 lengths.  
KimLock® cable laid resin terminated sling; 132mm dia; CSBL 827 MT; nominal length 70.60 m; x3 lengths.  
KimLock® cable laid resin terminated sling; 132mm dia; CSBL 827 MT; nominal length 46.00 m; x4 lengths.  
KimLock® cable laid resin terminated sling; 132mm dia; CSBL 827 MT; nominal length 40.00 m; x6 lengths.

Manufactured and tested at KTL Offshore (Malaysia) Sdn Bhd and witnessed by ABS.

