

PROJECT TITLE

AL WASIT - LTA Project (ME)

DATE

OCTOBER 2014.

BACKGROUND

Al Wasit project off the Saudi Arabian shores. This complex endeavor includes the design and construction of 12 wellheads, 2 tie-in and 1 injection platforms, a 260 km export trunkline offshore, a 120 km onshore pipeline, many service pipelines and cables, as well as the shore approaches. Due to the complex nature of the heavy lift, the length tolerance of the slings was very tight – only 2" allowed at the specified load. All slings met this stringent requirement and the lift was successfully completed.



AL WASIT - LTA Project (Saudi Arabian) Cable Laid Slings

ITEMS

- 1 x Cable Laid Sling (hand spliced) 283mm x 57.40 mtr length, CSBL 3224MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 80.3 mtr length, CSBL 4299MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 83 mtr length, CSBL 4299MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 57.70 mtr length, CSBL 3224MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 57.10 mtr length, CSBL 3224MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 80.10 mtr length, CSBL 3224MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 83.15 mtr length, CSBL 3224MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 58 mtr length, CSBL 3224MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 85.35 mtr length, CSBL 2969MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 51.50 mtr length, CSBL 2969MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 51.50 mtr length, CSBL 2969MT
- 1 x Cable Laid Sling (hand spliced) 283mm x 85.35 mtr length, CSBL 2969MT

All manufactured and tested by KTL Offshore in Singapore.
Witnessed and certified by ABS.

