

PROJECT TITLE
2915 Metric Ton Stinger Block and Sheaves

DATE
April 2015

BACKGROUND

The vessel, named *Derrick Lay Vessel* is equipped to support advanced deepwater pipelay operations that will allow pipelines to be installed at depths of up to 10,000 feet. An economical vessel transit speed is expected to be 12 knots with a top speed of 14 knots. KTL Offshore supplied RopeBlock Stinger & Strong back blocks and RopeBlock Tension block on board the vessel.



**2195 MT STINGER & STRONG BACK RIGGING BLOCKS AND TENSION BLOCK
Derrick Lay Vessel**



ITEMS

- 2 x 7+7 RopeBlock Sheave Stinger Block SWL 2915 MT
 - 1 x 8+7 RopeBlock Sheave Strong Back Block SWL 2915 MT
 - 1 x 8+7 RopeBlock Sheave Strong Back Block SWL 2915 MT
 - 1 x 1000T RopeBlock Tension Rigging block with double GS30MN5V Cast Sheaves
 - 2 x KimLift Round Slings, 180mm x 8mtr, MBL 1172MT
- All supplied by KTL Offshore in Singapore.
Witnessed and certified by **ABSG Consulting** and **ABS**.



71 Tuas Bay Drive
Singapore 637430
www.ktlgroup.com

Tel: (65) 6543 8888
Fax: (65) 6545 2323
Email: ktl@ktlsg.com.sg

MEMBER OF

